



## Bid Notice Abstract

### Invitation to Bid (ITB)

**Reference Number** 8406012  
**Procuring Entity** MANAOAG WATER DISTRICT  
**Title** EXPLORATORY DRILLING OF ONE (1) PRODUCTION WELL WITH 150M DEPTH X 200MM DIA. PILOT HOLE AT BRGY. BARITAO, MANAOAG, PANGASINAN  
**Area of Delivery** Pangasinan

<b>Solicitation Number:</b>	PRS#9577	<b>Status</b>	<b>Closed</b>
<b>Trade Agreement:</b>	Implementing Rules and Regulations	<b>Associated Components</b>	1
<b>Procurement Mode:</b>	Public Bidding	<b>Bid Supplements</b>	0
<b>Classification:</b>	Civil Works	<b>Document Request List</b>	4
<b>Category:</b>	Well Drilling and Construction Services	<b>Date Published</b>	08/02/2022
<b>Approved Budget for the Contract:</b>	PHP 6,500,000.00	<b>Last Updated / Time</b>	08/02/2022 00:00 AM
<b>Delivery Period:</b>	90 Day/s	<b>Closing Date / Time</b>	15/02/2022 11:00 AM
<b>Client Agency:</b>			
<b>Contact Person:</b>	Marlene Constanca Manaois Bac Chairperson Aquino St. Manaoag Pangasinan Philippines 2430 63-075-09209766271  marcons_manaois@yahoo.com.ph		

#### Description

EXPLORATORY DRILLING OF ONE (1) PRODUCTION WELL WITH 150M DEPTH X 200MM DIA. PILOT HOLE AT BRGY. BARITAO, MANAOAG, PANGASINAN

#### BILL OF QUANTITIES

##### WORK ITEM ESTIMATED TOTAL QUANTITY

- 1 Mobilization of equipment including drilling machine 1 No.
- 2 Preparation of site 1 No.
- 3 Drilling of pilot hole 200mm - Ø from ground surface to 150 meters depth 150 M.
- 4 Logging of pilot hole 1 No.
- 5 Reaming of pilot hole from 200mm - Ø 300mm - Ø borehole 150 M.
- 6 Furnishing of B.I blank steel casing with nominal diameter of 200mm and minimum wall thickness of 6mm 129 M.
- 7 Furnishing of stainless continuous slot wedge wire wound screens with nominal diameter of 200mm 21 M.
- 8 Installation of casing and screens 150 M.
- 9 Furnishing & installation of gravel pack materials and fill pipe 135 M.
- 10 Treatment with mudnox/polyphosphate solution 1 No.
- 11 Development by high velocity water jetting 12 HRS.
- 12 Development by surging & bailing 24 HRS.
- 13 Development by airlifting 12 HRS.
- 14 Step drawdown pumping test, Q 1 No.
- 15 Continuous discharge test, Q 72 HRS.
- 16 Cement grouting around annulus 15 M.
- 17 Well completion 1 No.
- 18 Demobilization and site clean-up 1 No.
- 19 Test results and reports 1 No.

TOTAL PRICE (Items No.1-19 including taxes): Php 6,500,000.00

TOTAL PRICE (in words): Six million five hundred thousand pesos

#### Pre-bid Conference

Date

Time

Venue

09/02/2022	2:00:00 PM	MANAOAG WATER DISTRICT OFFICE
------------	------------	-------------------------------

**Created by** Cecilia Mata Pinpin

**Date Created** 07/02/2022

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.

© 2004-2023 DBM Procurement Service. All rights reserved.

[Help](#) | [Contact Us](#) | [Sitemap](#)