



## Bid Notice Abstract

### Invitation to Bid (ITB)

**Reference Number** 8946154  
**Procuring Entity** MANAOAG WATER DISTRICT  
**Title** Supply of Labor and Materials for the Pipelaying and Water Supply Expansion Projects at Barangays San Ramon and Mermer, Manaoag, Pangasinan  
**Area of Delivery** Pangasinan

|  |   |                              |                     |
|--|---|------------------------------|---------------------|
| <b>Solicitation Number:</b>              | prs#9905  | <b>Status</b>                | <b>Closed</b>       |
| <b>Trade Agreement:</b>                  | Implementing Rules and Regulations  | <b>Associated Components</b> | 1                   |
| <b>Procurement Mode:</b>                 | Public Bidding  | <b>Bid Supplements</b>       | 0                   |
| <b>Classification:</b>                   | Goods   | <b>Document Request List</b> | 8                   |
| <b>Category:</b>                         | Water Service Connection Materials/Fittings   | <b>Date Published</b>        | 23/08/2022          |
| <b>Approved Budget for the Contract:</b> | PHP 7,500,000.00  | <b>Last Updated / Time</b>   | 23/08/2022 00:00 AM |
| <b>Delivery Period:</b>                  | 90 Day/s  | <b>Closing Date / Time</b>   | 31/08/2022 11:00 AM |
| <b>Client Agency:</b>                    |   |                              |                     |
| <b>Contact Person:</b>                   | Marlene Constanca Manaois<br>Bac Chairperson<br>Aquino St.<br>Manaoag<br>Pangasinan<br>Philippines 2430<br>63-075-09209766271<br><br>marcons_manaois@yahoo.com.ph |                              |                     |

#### Description

Supply of Labor and Materials for the Pipelaying and Water Supply Expansion Projects at Barangays San Ramon and Mermer, Manaoag, Pangasinan

#### BILL OF QUANTITIES (BOQ)

Item No. Description Unit Quantity Unit Cost Total Cost

#### A PIPELINES AND APPURTENANCES

##### A.1 Transmission Pipelines

a. 150mm (6") uPVC Pipes Series 8 Mechanical Seal (machine installed Integrated Seal of EPDM Rubber with metal reinforcement); conform to requirements of the Philippine National Standard Specifications for Unplasticized Polyvinyl Chloride (uPVC) pipes for Potable Water Supply (PNS 65 – Technical Standard Specification) and approved by the Bureau of Product Standards (BPS) LM 1050

b. 100mm (4") uPVC Pipes Series 8 Mechanical Seal (machine installed Integrated Seal of EPDM Rubber with metal reinforcement); conform to requirements of the Philippine National Standard Specifications for Unplasticized Polyvinyl Chloride (uPVC) pipes for Potable Water Supply (PNS 65 – Technical Standard Specification) and approved by the Bureau of Product Standards (BPS) LM 270

c. 75mm (3") uPVC Pipes Series 8 Mechanical Seal (machine installed Integrated Seal of EPDM Rubber with metal reinforcement); conform to requirements of the Philippine National Standard Specifications for Unplasticized Polyvinyl Chloride (uPVC) pipes for Potable Water Supply (PNS 65 – Technical Standard Specification) and approved by the Bureau of Product Standards (BPS) LM 2460

##### A.2 "Valves and Fittings

Brass / Ductile Iron / Cast Iron with PN16 – PN25 Pressure Rating, Industrial Grade"

a. 15% Total Pipeline Cost (maximum) LS 1

##### A.3 APPURTENANCES

a. Blow-off valve 75mm EA 3

b. Air release valve 50mm EA 1

##### A.4 BRIDGE / CULVERT CROSSING / FABRICATED FITTINGS / SUPPORTS

a. 150mm (6") B.I. Pipe (Schedule 40 STD) LM 150

c. 75mm (3") B.I. Pipe (Schedule 40 STD) LM 42

##### A.5 PAVEMENT DEMOLITION AND RESTORATION

a. Concrete pavement demolition LM 100

- b. Concrete surface restoration CUM 3.75
- c. Sand bedding CUM 992

TOTAL A:

**B WATER TREATMENT / HYDROTESTING**

- 1 "Pipe disinfection
- Hydrotest: 120 psi for at least 24- hours" LS 1

TOTAL B:

**C LABOR**

- 1 Excavation and backfilling LM 3972
- 2 Pipelaying, Interconnection, Cross Roads, Bridge Crossing
- 6" Pipe LM 1200
- 4" Pipe LM 270
- 3" Pipe LM 2502

TOTAL C

TOTAL COST

TOTAL ABC 7,500,000.00

**Pre-bid Conference**

| Date       | Time       | Venue                        |
|------------|------------|------------------------------|
| 26/08/2022 | 9:00:00 AM | Manoag Water District Office |

**Created by** Cecilia Mata Pinpin

**Date Created** 22/08/2022

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.